



CONCEPT, NOT FOR FABRICATION

SnapFrame · github.com/BoujeeEnjinia1701/snapframe




TOP VIEW

Scale 1:50; looking down (along -Z)




FRONT VIEW

Scale 1:50; looking at the front (along +Y)




RIGHT VIEW

Scale 1:50; looking at the right side (along -X)




ISOMETRIC VIEW

Not to scale; seen from the front right and above, about 30 deg elevation




EAVE NODE, ALL SIX (6)

Detail, not to scale



RIDGE NODE, END (7)

Detail, not to scale



FOOT NODE (5)

Detail, not to scale

KEY DIMENSIONS AND DATA (SIZE M)

Floor 4.0 x 4.0 m, bays 2 x 2.0 m; eave 1.8 m, ridge 2.6 m (node centers)
Cut lengths: post 1650, rafter 2064, ridge and eave 1910 mm
Tubes: 1 in EMT rafters and ridge (OD 29.5 mm); 3/4 in EMT posts and eaves (OD 23.4 mm)
Sockets: 65 mm engagement, bore = tube OD + 0.6 mm, wall 5 mm; core 84 mm
Button hole 6 mm at 40 mm from tube end, in a 16 mm finger recess; pin hole 8 mm at 15 mm
Foot plate 170 x 170 x 12 mm, two 18 mm anchor slots at 45 deg; anchor eye down on the plate
Eave and ridge nodes: M10 cable bolt with spacer and 6 mm ring; cables clip to rings and anchor eyes
Guy anchors 1.5 m beyond each gable; 10 brace cables, 4 mm
Wind rating 19.5 m/s at SF 1.5 (post governs, frame analysis); not rated for snow
Corner eave nodes: socket past the gable left blank and capped
Folding step (15) and two 560 mm rear anchors (16) not drawn

SNAPFRAME

github.com/BoujeeEnjinia1701/snapframe

General arrangement, size M

DRAWING NO. SNF-DWG-001		REV P5	SHEET 1 of 1	SIZE ANSI B
SCALE 1:50	UNITS mm	PROJECTION 	DATE 2026-10-02	DRAWN Amish Chadha
MATERIAL / NOTES EMT to ANSI C80.3; nodes printed in filled PA12-class nylon; see bom/bom.csv and SNF-CAL-001				
Licensed CERN-OHL-S-2.0 · Design Molecule Lab · designmolecule.com			Generated from cad/src; do not edit by hand	